DOOR SCHEDULE

DOOR										FRAME							REMARKS
No.	ROOM NAME	SIGN TYPE	TYPE	W	H	THK	MATL	FINISH	FIRE-RATING	TYPE	MATL	FINISH	HEAD	JAMB	SILL	HDWR SET	
212.8	FILM LOADING	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2		9	LIGHT SEALS
213	ART HISTORY SEMINAR	A-2	G	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	F	1	
214	RENDERING SERVER	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	F	6	
215	COMPUTER TEACHING LAB	A-2	G	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	G	1	
216	COMPUTER TEACHING LAB	A-2	G	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	G	1	
217	COMPUTER TEACHING LAB	A-2	G	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	G	1	
218	COMPUTER TEACHING LAB	A-2	G	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	G	1	
219	PRINTER ROOM	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	E	6	
220	DESIGN CENTER	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	E	1	
221	GRAPHIC ARTS STUDIO	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	E	1	
221.1	GRAPHIC ARTS STORAGE	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	E	9	
222	BOOK ARTS & FRAMING LAB	A-2	G	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	E	1	
222.1	BOOK ARTS STORAGE	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	E	9	
223	GRAPHIC DESIGN DIRTY ROOM	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	E	1	
224	ART HISTORY CLASSROOM	A-2	G	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	F	1	
225	TECH OFFICE	A-1	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	F	7	
226	COMPUTER STORAGE	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	E	6	
227	ADMINISTRATION	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	E	7	
227.1	MACHINE	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	E	9	SOUND RATED SEALS
227.2	STORAGE	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	E	9	
227.3	CONTROL ROOM B	A-2	V	3'-0"	7'-0"	1-3/4"	ST	P			ST	P			E	9	ACOUSTICAL DR. STC 55
227.4	ISOLATION STORAGE	A-2	V	3'-0"	7'-0"	1-3/4"	ST	P			ST	P			E	9	ACOUSTICAL DR. STC 55
227.5	CONTROL ROOM A	A-2	V	3'-0"	7'-0"	1-3/4"	ST	P			ST	P			E	9	ACOUSTICAL DR. STC 55
227.6	LIVE ROOM	A-2	V	3'-0"	7'-0"	1-3/4"	ST	P			ST	P			E	9	ACOUSTICAL DR. STC 55
228	JANITOR	A-2	F	PR 3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	E	11	
229	AV STORAGE	A-2	F	PR 3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	E	11	
230	PAINTING STUDIO	A-2	G	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	E	1	
230A	PAINTING STUDIO	A-2	G	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	E	1	
230.1	CHANGING	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	E	9	
230.2	DRAWING STORAGE	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	E	9	
232	AV STORAGE	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	E	11	
2E1	ELECTRICAL	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	E	8	
2E2	ELECTRICAL	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	E	8	
2ST2	STAIR 2	A-2	V	3'-0"	7'-0"	1-3/4"	SC WD	P	90 MIN	2	ST	P	H3	J3	E	6	A-4 SIGN TYPE REQUIRED
2ST3	STAIR 3	A-2	V	3'-0"	7'-0"	1-3/4"	SC WD	P	60 MIN	2	ST	P	H3	J3	E	6	A-4 SIGN TYPE REQUIRED
2ST4	STAIR 4	A-2	V	3'-0"	7'-0"	1-3/4"	SC WD	P	60 MIN	2	ST	P			E	6	A-4 SIGN TYPE REQUIRED
2ST4A	STAIR 4	A-2	V	3'-0"	7'-0"	1-3/4"	SC WD	P	60 MIN	2	ST	P			E	6	
2ST5	STAIR 5	A-2	V	3'-0"	7'-0"	1-3/4"	SC WD	P	60 MIN	2	ST	P			E	6	A-4 SIGN TYPE REQUIRED
2ST5A	STAIR 5	A-2	V	3'-0"	7'-0"	1-3/4"	SC WD	P	60 MIN	2	ST	P			E	6	
2T1	TELECOM	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	E	8	
2T2	TELECOM	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	E	8	
301	CONFERENCE ROOM	A-2	G	3'-0"	7'-0"	1-3/4"	SC WD	P		4	ST	P	H2	J2	D	1	
301A	CONFERENCE ROOM	A-2	G	3'-0"	7'-0"	1-3/4"	SC WD	P		4	ST	P	H2	J2	D	1	
302	STORAGE	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	D	12	
303	MIRANDA FACULTY OFFICE	A-1	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	D	7	
304	ALLYN FACULTY OFFICE	A-1	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	D	7	
305	MACKIE FACULTY OFFICE	A-1	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	D	7	
306	SANDERS FACULTY OFFICE	A-1	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	D	7	
307	CHAK FACULTY OFFICE	A-1	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	D	7	
308	KAPLOWITZ FACULTY OFFICE	A-1	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	D	7	
309	ADJUNCT FACULTY OFFICE	A-1	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	D	7	
310	ROSE FACULTY OFFICE	A-1	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	D	7	
311	ADJUNCT FACULTY OFFICE	A-1	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	D	7	
312	ADJUNCT FACULTY OFFICE	A-1	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	D	7	
3M1.1	JANITOR	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	H	5	
314	WOMEN	A-3	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	H	5	
315	KABBASH FACULTY OFFICE	A-1	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	D	7	
316	VAN DER HEIJDEN FACULTY OFFICE	A-1	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	D	7	
317	AULT FACULTY OFFICE	A-1	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	D	7	
318	CUNNINGHAM FACULTY OFFICE	A-1	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	D	7	
319	LOUNGE	A-2	G	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	A	6	
320	RECEPTION / WAITING AREA	A-2	G	3'-0"	7'-0"	1-3/4"	SC WD	P		5	ST	P	H2	J2	D	7	
320.1	CLOSET	A-2	G	3'-0"	7'-0"	1-3/4"	SC WD	P		5	ST	P	H2	J2	D	7	
321	ADMIN OFFICE	A-1	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	D	9	
322	CO-CHAIR OFFICE	A-1	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	D	9	
323	CHAIR OFFICE	A-1	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	D	9	
324	SLIDE LIBRARY	A-2	G	3'-0"	7'-0"	1-3/4"	SC WD	P		5	ST	P	H2	J2	D	1	
324A	SLIDE LIBRARY	A-2	G	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	D	9	
325	COPY	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	D	6	
326	FACULTY OFFICE	A-1	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	D	7	
327	HUTTON FACULTY OFFICE	A-1	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	D	7	
328	FACULTY OFFICE	A-1	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	D	7	
329	JOYCE FACULTY OFFICE	A-1	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	D	7	
330	MEN	A-3	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	D	5	
3M2.1	JANITOR	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	D	5	
332	ADJUNCT FACULTY OFFICE	A-1	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	D	7	
333	ADJUNCT FACULTY OFFICE	A-1	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	D	7	
334	ADJUNCT FACULTY OFFICE	A-1	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	D	7	
335	ADJUNCT FACULTY OFFICE	A-1	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	D	7	
336	RIGBY FACULTY OFFICE	A-1	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	D	7	
337	FICHNER-RATHUS FACULTY OFFICE	A-1	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	D	7	
338	MILLER FACULTY OFFICE	A-1	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	D	7	
339	NYMAN FACULTY OFFICE	A-1	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	D	7	
340	RICCARDI FACULTY OFFICE	A-1	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	D	7	
341	FACULTY OFFICE	A-1	F	3'-0"	7'-0"	1-3/4"	SC WD	P	45 MIN	1	ST	P	H2	J2	D	7	
343	AREA OF REFUGE	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P	20 MIN	1	ST	P	H2	J2	F	6	A-4 SIGN TYPE REQUIRED
344	AREA OF REFUGE	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P	20 MIN	1	ST	P	H2	J2	F	6	A-4 SIGN TYPE REQUIRED
3C2	CORRIDOR (EXTERIOR)	A-2	F	3'-0"	7'-0"	1-3/4"	ST	P			AL					2A	
3C4	CORRIDOR (EXTERIOR)	A-2	F	3'-0"	7'-0"	1-3/4"	ST	P			AL					2A	
3E1	ELECTRICAL	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	E	8	
3E2	ELECTRICAL	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	E	8	
3M1	MECHANICAL	A-2	F	PR 3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	F	3A	
3M2	MECHANICAL	A-2	F	PR 3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	F	3A	
3ST2	STAIR 2	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P	90 MIN	1	ST	P	H2	J2	E	6	A-4 SIGN TYPE REQUIRED
3ST3	STAIR 3	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P	60 MIN	1	ST	P	H2	J2	E	6	A-4 SIGN TYPE REQUIRED
3T1	TELECOM	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	E	8	
3T2	TELECOM	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	E	8	

DOOR SCHEDULE

DOOR										FRAME							REMARKS
No.	ROOM NAME	SIGN TYPE	TYPE	W	H	THK	MATL	FINISH	FIRE-RATING	TYPE	MATL	FINISH	HEAD	JAMB	SILL	HDWR SET	
B01	RECYCLING STORAGE	A-2	F	PR 3'-0"	7'-0"	1-3/4"	ST	P		2	ST	P	H1	J1	E	11	
B01A	RECYCLING STORAGE	A-2	F	PR 3'-0"	7'-0"	1-3/4"	ST	P		2	ST	P	H1	J1	E	11	
B02	AV STORAGE	A-2	F	PR 3'-0"	7'-0"	1-3/4"	ST	P		2	ST	P	H1	J1	E	6	
B03	MEN	A-3	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H1	J1	B	5	
B04	WOMEN	A-3	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H1	J1	B	5	
BE1	MAIN ELEC	A-2	F	PR 3'-0"	7'-0"	1-3/4"	ST	P	90 MIN	2	ST	P	H1	J1	E	11	ASTRAGAL
BE1A	MAIN ELEC	A-2	F	3'-0"	7'-0"	1-3/4"	ST	P	90 MIN	2	ST	P	H1	J1	E	11	
BE2	GENERATOR	A-2	F	PR 3'-0"	7'-0"	1-3/4"	ST	P	3 HR	2	ST	P	H1	J1	E	11	ASTRAGAL
BC1	CORRIDOR (EXTERIOR)	A-2	F	PR 3'-0"	7'-0"	1-3/4"	ST	P		2	ST	P	H5	J5	I	3A	
BM1	MECHANICAL	A-2	F	PR 3'-0"	7'-0"	1-3/4"	ST	P		2	ST	P	H1	J1	E	11	
BM1A	MECHANICAL	A-2	F	3'-0"	7'-0"	1-3/4"	ST	P		2	ST	P	H1	J1	E	8	
BM2	NOT USED																
BM3	NOT USED																
BM4	ELEV. MACHINE	A-2	F	3'-0"	7'-0"	1-3/4"	ST	P	90 MIN	2	ST	P	H1	J1	E	8	
BM5	MECHANICAL	A-2	F	3'-0"	7'-0"	1-3/4"	ST	P		2	ST	P	H1	J1	E	8	
BT1	MAIN TEL/COM	A-2	F	3'-0"	7'-0"	1-3/4"	ST	P	90 MIN	2	ST	P	H1	J1	E	8	
BST6	STAIR 6	A-2	V	3'-0"	7'-0"	1-3/4"	ST	P	60 MIN	2	ST	P	H1	J1	E	6	A-4 SIGN TYPE REQUIRED
BST2	STAIR 2	A-2	V	3'-0"	7'-0"	1-3/4"	ST	P	90 MIN	2	ST	P	H1	J1	E	6	A-4 SIGN TYPE REQUIRED
101	LOBBY		FG	PR 3'-10"	9'-0"	1-3/4"	AL	P			AL	P			E	4	ENTRANCE DOORS
101.1	VESTIBULE (EXTERIOR)		FG	PR 3'-10"	9'-0"	1-3/4"	AL	P			AL	P			I	3	ENTRANCE DOORS
101.2	AV	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	E	6	
102	ART EDUCATION	A-2	G	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	E	1	
102.1	ART EDUCATION STORAGE	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	E	9	
103	SHARED SEMINAR	A-2	G	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	F	1	
104	CERAMICS	A-2	G	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	E	1	
104.2	STORAGE	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	E	9	
105	TRASH/RECYCLE LOADING	A-2	F	PR 3'-0"	7'-0"	1-3/4"	SC WD	P		2	ST	P	H3	J3	E	10	
105A	TRASH/RECYCLE LOAD. (EXT.)		F	PR 3'-0"	7'-0"	1-3/4"	ST	P		2	ST	P	H4	J4	E	3A	
106	WOMEN	A-3	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	B	5	
107	MEN	A-3	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	B	5	
108	SCULPTURE STUDIO	A-2	F	PR 3'-0"	7'-0"	1-3/4"	SC WD	P		2	ST	P	H3	J3	E	11	
108A	SCULPTURE STUDIO (EXTERIOR)		F	PR 3'-0"	7'-0"	1-3/4"	SC WD	P		6	ST	P	H4	J4	I	3	
108B	SCULPTURE STUDIO (EXTERIOR)		F	PR 3'-0"	7'-0"	1-3/4"	SC WD	P		6	ST	P	H4	J4	I	3	
108C	SCULPTURE STUDIO	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		2	ST	P	H3	J3	E	1	
108.1	SCULPTURE STORAGE	A-2	D	PR 3'-0"	7'-0"	1-3/4"	SC WD	P		2	ST	P	H1	J1	E	11	
108.2	SCULPTURE STORAGE	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		2	ST	P	H1	J1	E	9	
108.3	PLASTER	A-2	G	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	E	9	
108E	DUST COLLECTION (EXTERIOR)	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		2	ST	P	H1	J1	I		
108E.1	DUST COLLECTION (EXTERIOR)	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		2	ST	P	H1	J1	I		
109	STUDENT STUDIOS	A-2	G	PR 3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	E	11	
109A	STUDENT STUDIOS (EXTERIOR)		FG	PR 3'-0"	7'-0"	1-3/4"	AL	P			AL	P			I	3	ENTRANCE DOORS
110	STUDENT LOUNGE (EXTERIOR)		FG	PR 3'-0"	7'-0"	1-3/4"	AL	P			AL	P			I	3	ENTRANCE DOORS
111	RECYCLING / JANITOR	A-2	F	PR 3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	E	11	
112	INSTALLATION SPACE	A-2	F	PR 3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	E	11	
113	EXHIBITION SPACE	A-2	G	PR 3'-0"	7'-0"	1-3/4"	SC WD	P		3	ST	P	H2	J2	E	11	SEGMENTED
113A	EXHIBITION SPACE (EXTERIOR)		FG	PR 3'-0"	7'-0"	1-3/4"	AL	P			AL	P			I	3	
113B	EXHIBITION SPACE (EXTERIOR)		FG	PR 3'-0"	7'-0"	1-3/4"	AL	P			AL	P			I	3	
114	INSTALLATION SPACE	A-2	F	PR 3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	E	11	
115	EXHIBITION STORAGE	A-2	F	PR 3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	E	11	
115.1	SECURE STORAGE	A-2	CL	3'-0"	7'-0"	1-3/4"	ST	GALV			ST	GALV					CHAIN LINK
116	GRAPHIC STUDIO	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	E	1	
116A	GRAPHIC STUDIO (EXTERIOR)		FG	PR 3'-0"	7'-0"	1-3/4"	AL	P			AL	P			I	3	ENTRANCE DOORS
117	STUDENT STUDIOS	A-2	G	PR 3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	E	11	
117A	STUDENT STUDIOS (EXTERIOR)		FG	PR 3'-0"	7'-0"	1-3/4"	AL	P			AL	P			I	3	ENTRANCE DOORS
118	PRINTMAKING STUDIO	A-2	G	PR 3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	E	11	
118A	PRINTMAKING STUDIO	A-2	G	PR 3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	E	11	
118.1	MORDANT / SOLVENT ROOM	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	E	9	
118.2	ALTERNATIVE DARKROOM /	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	E	9	
118.2A	SCREEN COATING & ENCL. RM.	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	E	9	
118.3	PRINTMAKING STORAGE	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	E	9	
119	PAPERMAKING STUDIO	A-2	G	3'-0"	7'-0"	1-3/4"	SC WD	P		2	ST	P	H3	J3	E	1	
119A	PAPERMAKING STUDIO (EXTERIOR)		F	PR 3'-0"	7'-0"	1-3/4"	SC WD	P		2	ST	P	H4	J4	I	3	
119.1	BEATER ROOM	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		2	ST	P	H2	J2	E	9	
119.2	PAPERMAKING STORAGE	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		2	ST	P	H1	J1	E	9	
120	DESIGN	A-2	G	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	E	1	
120.1	DESIGN STORAGE	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	E	9	
120.1A	DESIGN STORAGE	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	E	9	
121	DRAWING STUDIO	A-2	G	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	E	1	
121.1	CHANGING	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	E	9	
121.2	PAINTING STORAGE	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	E	9	
122	AV STORAGE	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		2	ST	P	H3	J3	E	6	
1C1	CORRIDOR (EXTERIOR)		FG	3'-0"	7'-0"	1-3/4"	AL	P			AL	P			I	2A	ENTRANCE DOORS
1C2	CORRIDOR		F	PR 3'-8"	7'-0"	1-3/4"	SC WD	P	60 MIN	2	ST	P			E	10	
1C3	CORRIDOR (EXTERIOR)		FG	3'-0"	7'-0"	1-3/4"	AL	P			AL	P			I	2A	
1C4	CORRIDOR		F	PR 3'-8"	7'-0"	1-3/4"	SC WD	P	60 MIN	2	ST	P			E	10	
1ST2	STAIR 2	A-2	V	3'-0"	7'-0"	1-3/4"	SC WD	P	90 MIN	2	ST	P	H3	J3	E	6	A-4 SIGN TYPE REQUIRED
1ST2A	STAIR 2 (EXTERIOR)	A-4	FG	4'-0"	7'-0"	1-3/4"	AL	P			AL	P			I	2A	
1ST3A	STAIR 3	A-2	V	3'-0"	7'-0"	1-3/4"	SC WD	P	60 MIN	2	ST	P	H3	J3	E	6	
1ST3A	STAIR 3 (EXTERIOR)	A-4	FG	4'-0"	7'-0"	1-3/4"	AL	P			AL	P			I	2A	
1ST4	STAIR 4 (EXTERIOR)		FG	3'-0"	7'-0"	1-3/4"	AL	P			AL	P			I	2A	
1ST5	STAIR 5 (EXTERIOR)		FG	3'-0"	7'-0"	1-3/4"	AL	P			AL	P			I	2A	
1ST6	STAIR 6		F	3'-0"	7'-0"	1-3/4"	SC WD	P	60 MIN	2	ST	P	H3	J3	E	6	
1E1	ELECTRICAL	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		2	ST	P	H3	J3	E	8	
1E2	ELECTRICAL	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		2	ST	P	H3	J3	E	8	
1T1	TELECOM	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		2	ST	P	H3	J3	E	8	
1T2	TELECOM	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		2	ST	P	H3	J3	E	8	
1SY	SCULPTURE YARD		CL	3'-8"	9'-0"		ST	GALV			ST	GALV					
1PS	OUTDOOR PAPER STUDIO		CL	3'-8"	9'-0"		ST	GALV			ST	GALV					
201	COMPUTER TEACHING LAB	A-2	G	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	G	1	
202	LARGE FORMAT PRINTER ROOM	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	E	6	
203	LIGHTING STUDIO	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2		1	
203A	LIGHTING STUDIO	A-2	F	PR 3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2		11	
204	GRANTS & RESEARCH LAB	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	E	6	
205	UBIQUITOUS COMPUTING LAB	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	E	1	
205.1	UBIQ. COMP. LAB STORAGE	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	E	9	
206	WOMEN	A-3	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	B	5	
207	MEN	A-3	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	B	5	
208	CAGE	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	E	6	
209	PHOTO CLASSROOM	A-2	G	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	G	1	
210	MYLOWE OFFICE	A-1	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	E	7	
211	SHARED CLASSROOM	A-2	G	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	F	1	
212	CENTRAL PROCESSING WET/DRY	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	E	1	
212.1	DARKROOM STORAGE	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2	E	9	
212.2	LIGHT LOCK	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2		9	LIGHT SEALS
212.5	FILM LOADING	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2		9	LIGHT SEALS
212.6	FILM LOADING	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2		9	LIGHT SEALS
212.7	FILM LOADING	A-2	F	3'-0"	7'-0"	1-3/4"	SC WD	P		1	ST	P	H2	J2		9	LIGHT SEALS

1 DOOR SCHEDULE
A901 A901 SCALE: NONE

EYP/

Einhorn Yaffee Prescott
Architecture & Engineering, P.C.
1000 Potomac Street, NW
Washington, D.C. 20007
Telephone: 202.471.5000
Fax: 202.471.5050

eypae.com

KEY PLAN:

1 ADDENDUM #3 4.1.2008

NO. REVISION/SUBMISSION DATE

THE COLLEGE OF NEW JERSEY

New Art & IMM Building

Ewing, New Jersey

DATE: 2.20.2008
SCALE: NONE
EYP PROJECT NO. 1006041.01
DESIGNED BY:
DRAWN BY:
CHECKED BY:

Matthew S. Chalifoux
NEW JERSEY REGISTERED ARCHITECT
LICENSE NO. 10016

DOOR SCHEDULE

A901

© 2007 Einhorn Yaffee Prescott, A&E